Notice dated 18th June 1929.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 27th June 1929, Part VI, pages 635 and 636, calling for tenders for Restoring Mangasandra Vottikere, Kolar Taluk.

The last date of tender is 12th July 1929.

Notice dated 19th June 1929.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 27th June 1929, Part VI, pages 637 and 638, calling for tenders for Restoring Hirengavalli Jonalkunte Tank, Chikballapur Taluk.

The last date of tender is 12th July 1929.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 30th June 1929.

RESTORING BOMMENAHALLI TANK (MINOR) REGISTERED No. 186, TURUVEKERE SUB-TALUK.

Attention is drawn to notification on pages 661 and 662 of Part VI in the *Mysore Gazette*, dated 4th July 1929, calling for tenders for restoring Bommenahalli tank (Minor) Registered No. 186, Turuvekere Sub-Taluk. Earnest money Rs. 150.

Last date of receiving tenders 2 P.M. of 30th July 1929.

Abstract Notification dated 20th June 1929.

Attention of the public is drawn to the notification, published in pages 642 and 643 of the *Mysore Gazette*, dated 27th June 1929, calling for tenders for Restoring Thovinkere Ganikere Tank, Registered No. 226 of Kortagere Taluk.

The last date for submission of the tender is 15th July 1929, 2 P.M.

V. V. PATANKAR,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 24th June 1929.

The attention of the public is invited to the notice calling for tenders for maintenance work of Yagati Tank, published in pages 643 and 644 of Part VI of the *Mysore Gazette*, dated 27th June 1929, the last date for receiving tender is 20th July 1929.

B. KRISHNA RAO,
Executive Engineer.

HASSAN DIVISION.

Dated 4th July 1929.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 3 P.M. on 18th July 1929, for constructing Urdu Middle School at Hassan. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in Cash or Government promissory notes as earnest money, and be superscribed "Tender for constructing Urdu Middle School at Hassan", in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending or Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing an Urdu Middle School Building at Hassan. "Two wings to be constructed". For one wing.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in	C.yd.	14
2	Burnt stone in clay foundation	C.ft.	586
3	Superstructure (brick in clay)	,,	762
4	Burnt brick in chunnam arch work	,,	17
5	Brick in chunnam	,,	71
6	Burnt stone slabs 6" thick	S.ft.	76
7	Teakwood work wrought and put up with oiling	C.ft.	43 6
8	Roofing with Mangalore tiles on teak reepers and nails, etc.	Sqr.	7·37
9	Ridge tiles set in mortar	R.ft.	26
10	Rough plastering one coat ½" thick, well rubbed with trowe and pressed with pebbles from sand screenings.	Sqr.	19·50
11	White washing	,,	19·50
12	Perforated brick work	Lump	sum
13	Tarring wood work	Lump	sum
14	Flooring with square Mangalore tiles on 3" metal concrete and cement pointing.	Sqr.	3·07
15	Flooring with Cuddappa slabs on 3" metal concrete and cement pointing	,,	0·79
16	Jungle wood eave board with painting	R.ft.	103½
17	Cement pointing to basement	Sqr.	1·22
18	Ornamental work	Lump	sum
19	Chunnam borders	R.ft.	100
20	Clearing site and unforeseen	Lump	sum
21	Cutting "u" shape in stone pillars	Each	2
22	Finials and buds	,,	4

Abstract estimate for constructing an Urdu Middle School Building at Hassan. "Two wings to be constructed" For Central block.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in	C.yd.	49
2	Burnt stone in clay fundation and basement	C.ft.	2,045
3	Burnt brick in clay superstructure	,,	2,828
4	Burnt brick in chunnam arch work	,,	90
5	Burnt brick in chunnam	,,	325
6	Burnt stone slabs	S.ft.	286
7	Teakwood doors	,,	140
8	Do windows	,,	119
9	Do glazed ventilators over windows	,,	36
10	Do wrought and put up	C.ft.	156·21
11	Roofing with mangalore tiles	Sqr.	28·15
12	Ridge tiles set in mortar	R.ft.	134
13	Valleys with teakwood planks, zinc sheet plain and cement work etc., complete.	,,	51
14	Rough plastering	Sqr.	64·74
15	White washing	,,	64·74
16	Silicate painting	,,	5·90
17	Tarring to wood work	Lump	sum
18	Flooring with Mangalore tiles on 3" metal concrete and cement pointing.	Sqr.	13·13
19	Flooring with Cuddappa slabs on 3" concrete and cement pointing.	,,	2·82
20	Jungle wood eave board	,,	218
21	Cement pointing to basement	,,	310
22	Ornamental work round windows	Lump	sum
23	Chunnam borders	Lump	sum
24	Clearing site and unforeseen	Lump	sum
25	Inscription stone	Lump	sum
26	Finials	No.	3
27	Cutting in "u" shape in stone pillars	,,	8
28	Panborated brick work	,,	